




# राजस्थान केन्द्रीय विश्वविद्यालय CENTRAL UNIVERSITY OF RAJASTHAN



No. CURAJ/R/F. 164/2025/3701

Date: 11.8 FEB 2025

## NOTICE INVITING QUOTATIONS

Sealed item rate quotations are invited from reputed firms / Contractors of CPWD, MES, BRO, State PWD or Public sector undertakings on behalf of Central University of Rajasthan for "**Construction of Selfie point at Central University of Rajasthan**" by the Registrar, Central University of Rajasthan, BandarSindri. Interested firms/contractors may obtain details from the university website [www.curaj.ac.in](http://www.curaj.ac.in).

The Quotations duly filled shall be submitted in Room No. 101, Ground Floor Administration Building, Central University of Rajasthan, on or before 21.02.2025 up to 2:00 P.M. The quotations shall be opened on the same day at 3:00 P.M. in the presence of bidders / or their authorized representative, who may be present. Quotations other than on the prescribed form as downloaded from the university website shall be summarily rejected.

**Name of Work:** - Construction of Selfie point at Central University of Rajasthan.

S.No.	Description of Item	Quantity	Rate	Unit	Amount
01-	----- As per Sheet attached (Annexure - A) -----				

### TERMS AND CONDITIONS:-


1. The participating firms / contractor should have experience in execution of similar works (attach relevant documents).
2. The work has been carried out as per Schedule of quantity.
3. Stipulated period for the completion of maintenance work 20 (Twenty) days from date of Work order failing which, penalty of Half Percent of work order value per week of delay subject to maximum 10% of work order value will be imposed.
4. Rates quoted shall be inclusive of all taxes such as GST, etc.
5. TDS will be applicable as per rules.

Registrar  
Central University of Rajasthan

**REGISTRAR**  
Central University of Rajasthan  
N.H.-8, Bandarsindri, Teh.-Kishangarh  
PIN-305 817 Distt.-Ajmer (Rajasthan) INDIA



# राजस्थान केन्द्रीय विश्वविद्यालय CENTRAL UNIVERSITY OF RAJASTHAN



Annexure - A

No. CURAJ/R/F. 164/2025/3701

Date: 18 FEB 2025


## SCHEDULE OF QUANTITY

**Name of Work:** - Construction of Selfie point at Central University of Rajasthan - reg.

S.No.	Description	Qty	Unit	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
1.1	All kinds of soil.	7.25	cum		
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	7.25	cum		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
3.1	1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources).	1.45	cum		
3.2	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources: 4 graded stone aggregate 20 mm nominal size derived from natural sources).	1.23	cum		
4	Providing and laying damp-proof course 40mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand derived from natural sources): 4 graded stone aggregate 12.5mm nominal size derived from natural sources)	2.94	sqm		
5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:				
5.1	Cement mortar 1:6 (1 cement : 6 coarse sand)	5.64	cum		
6	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, ifnishing and reinforcement- All work up to plinth level :				



# राजस्थान केन्द्रीय विश्वविद्यालय CENTRAL UNIVERSITY OF RAJASTHAN



6.1	1:1.5:3 (1 cement: 1.5 coarse sand (zone-III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources).	0.27	cum		
7	Centering and shuttering including strutting, propping etc. and removal of form work for :				
7.1	Foundations, footings, bases for columns	2.62	sqm		
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
8.1	Thermo-Mechanically Treated bars of grade Fe-500D or more.	53.08	kg		
9	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge.				
9.1	Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.	25.60	Sqm		
10	1- Providing and fixing 2mm thick SS 304 grade Stainless Steel with engraved Central University of Rajasthan logo of dia. 1 Mtr. to 1.2 Mtr. including SS frame bottom flat necessary nut bolt complete as per direction of the Engineer in- Charge. 2- Providing and fixing 2mm thick SS 304 grade Stainless Steel with engraved Central University of Rajasthan NAAC logo and " I love CURAJ" letter with appropriate size letters complete as per direction of Engineer-in-charge. Note: 1- Details justification with drawing shall be provided by the bidder.	1	Job		
<b>Gross Total</b>				<b>Rs.</b>	

**Registrar**  
**Central University of Rajasthan**  
**REGISTRAR**  
**Central University of Rajasthan**  
**N.H.-8, Bandarsindri, Teh.-Kishangarh**  
**PIN-305 817 Distt.-Ajmer (Rajasthan) INDIA**